

Hatched area indicates limits of 6" concrete when sidewalk is installed.  
The apron and the curb and gutter will be monolithic.  
All concrete will be Class A3.  
High early strength concrete to be used as directed by the inspector.

4-22-70

DE-1

## REVISIONS

**FAUQUIER COUNTY**

STANDARD  
DRIVEWAY ENTRANCE

DE-1