Wanda S. Suder, AICP Planner (703) 680-4664 Ext. 112 wsuder@pw.thelandlawyers.com Fax: (703) 680-2161

March 10, 2006

Melissa M. Dargis
Assistant Chief of Planning
Department of Community Development
Fauquier County
40 Culpeper Street
Warrenton, Virginia 22186

Re: REZN05-LE-001, SPEX05-LE-008, Freedom Place

Dear Melissa:

This letter contains the responses to the comments provided by the County Engineer and VDOT. The comments from the County Engineer dated February 23, 2006 and received on the same date have been formatted in the table below for ease of reference:

| Low Impact Development (LID) — the first and probably most important aspect of LID is to preserve natural drainage areas in their natural state. The applicant has done a good job of preserving the Bowens Run corridor, however, there are four significant drainage swales and a spring within the densely developed areas that should be preserved in their natural state. These were discussed previously with the engineer but are not preserved in this plan. The SWM/BMP's should be provided for the proposed "community use" area (possible fire department) with this development. | A modification has been submitted to the county to address the location of Natural Drainage/ Channels on site. The area identified as a spring by the county engineer has yet to be verified as an actual spring. The site will be investigated by the applicant's geotechnical engineer and if deemed to be a spring, the lot layout will be modified to protect the spring during the Plat/Site Plan process. A note has been added to the CDP to reflect that a SWM Pond will be provided to serve the proposed Fire Department. Until such time as final development plans are provided to the |
|--|--|
| | Applicant for the fire station and the actual SWM needs can be calculated, the pond area will function as a sediment control pond. |
| The alleys are shown in such a way that they will become stormwater collection areas. (Page 18 Planning and Design Guidelines) The alleys should be crowned and ditches or storm sewer pipes should be provided. Significant icing and flooding could occur with | The Applicant agrees to revise the alley cross section, as discussed in the staff meeting, to show a constant cross slope with storm sewer inlets provided along the lower curb side, which will address this concern. |

| the design presented. | |
|---|--|
| 1. Under no circumstances shall any use, activity, fill, and/or development within the floodplain adversely affect the capacity of the channels or floodways of any watercourse, drainage ditch or any other drainage facility or system which would increase flood heights and/or velocities on adjacent properties. | A note has been added to the CDP to address this comment. |
| 2. The proposed connections to Route 28 is to line up with the road connections on the south side of Route 28 as depicted on the final construction of Wexford Mews. These connections need to line up to facilitate traffic movement across Route 28. | According to the research completed before designing the CDP, the Church Street and the SW Access intersections along Route 28 were located as to align with the Wexford Mews plans. |
| 3. The following conditions should be required for the special exception for fill in the floodplain: | |
| a. The crossing shall be designed to accommodate all Federal, State, and Local requirements and shall incorporate rivertraining and counter-sinking techniques | This is understood and accepted as a condition by the Applicant. |
| b. The crossing shall not be sized any larger than necessary to convey the applicable design storms for the relevant category of roadway (based on traffic estimates) unless mutually agreed to and requested by the Fauquier County Engineering Office and VDOT. | This is understood and accepted as a condition by the Applicant. |
| c. In all cases, proposed crossings of the FEMA floodplain shall be aligned and designed to traverse floodplains and the natural stream in locations where disturbance to the floodplain is minimized. (i.e. – in areas where floodplain top widths are the smallest and where the natural stream can be crossed perpendicularly without requiring natural stream channel relocation unless otherwise directed by the County Engineer.) | The crossing to the proposed FEMA Floodplains will be in substantial conformance with the layout shown on the CDP. |
| d. Should multiple structures be required to accommodate the projected discharges, the primary cell of the crossing shall be sized to | This is understood and accepted as a condition by the Applicant. |

| conform to the natural streets sharestoristics | |
|--|--|
| conform to the natural stream characteristics | |
| (as defined by stream width, existing bed & | |
| banks, invert elevations, etc.) These | |
| characteristics must be field surveyed and be | |
| included with final plan submittal. The | |
| primary cell shall be located in the actual | · |
| location of the incised streambed. Additional | · . |
| cells of the crossing must be designed to only | |
| be activated at such time as the overbank | |
| region would normally be activated with | |
| higher volumes of stormwater runoff (as | |
| determined by the County Engineer). Invert | |
| elevations of the additional cells shall be | |
| established no lower than the natural overbank | |
| 1 | |
| elevation where they will be placed. Should | |
| the cells be constructed as a single structure, | |
| the crown elevation of all cells must be | |
| designed to match each other. Depending on | |
| the individual site conditions, the additional | · |
| cells may be constructed separately from the | |
| primary cells but must meet Fauquier County | |
| and VDOT requirements at the time of final | , |
| design review | |
| e. A detailed flood study must be prepared to | This is understood and accepted as a condition |
| County Specifications and submitted to FEMA | by the Applicant. A Flood Study and CLOMR |
| for CLOMR/LOMR processing. These items | will be completed prior to Final Subdivision |
| must be bonded with Fauquier County until | Plan approval for 1 st section submitted— |
| complete | LOMR is done AFTER development is done as |
| , | an Asbuilt and Final Map Rev |
| f. Proper permits are to be obtained from DEQ, | This is understood and accepted as a condition |
| DOE, and/or VMRC for any work in waters of | by the applicant. |
| the US and/or the state. | by the applicant. |
| | This is understood and seconted as a condition |
| g. The CLOMR must be approved prior to the | This is understood and accepted as a condition |
| approval of the final construction plans | by the Applicant. |
| 4. Stormwater management pond | This is understood and accepted as a condition |
| embankments are not to be in the floodplain. | by the Applicant. Please reference the CDP, a |
| | note has been added to reflect this comment. |
| 5. All applicable State and Federal permits are | This is understood and accepted as a condition |
| to be filed with the first submission of the Final | by the Applicant. Please reference the CDP, a |
| construction Plans. This includes the | note has been added to reflect this comment. |
| COE/DEQ wetlands permit. | |
| · · · · · · · · · · · · · · · · · · · | |

REZN05-LE-001, SPEX05-LE-008, Freedom Place Engineering/VDOT Response Letter March 10, 2006 Page 4 of 10

6. The County recommends that no below grade basements be constructed on soils with high water table due to wetness unless the foundation drainage system of the structure is designed by a licensed professional engineer to assure a dry basement and preclude wet yards and recirculation of pumped or collected water. Unless, in the opinion of the County Engineer, the topography of the lot in relation to the overlot-grading plan precludes grading the site to drain the basement to daylight, all basements shall be designed to gravity daylight without assistance from mechanical means. All discharged water (mechanical or gravity) must be conveyed to the subdivision stormwater collection system and discharged though the stormwater management faculties. Drainage easements, where necessary, shall be placed on the final plat. A note shall be placed on the final plat stating that "Basements are not recommended in mapping units 5A, 14B, 74B, 78A, and 79A. Basements in these mapping units are subject to flooding due to high seasonal water tables. Sump systems may run continuously, leading to possible premature pump failure." 7. Applicant should provide 100 year detention and 100 year overland relief to help mitigate against downstream flooding.

A proffer has been added to address the condition of below grade basements in areas of potentially high water table.

The Applicant acknowledges the County Engineer's concerns pertaining to the design of the subsurface systems to deal with potentially high groundwater. All designs and notes that will be required on Final Plats will be coordinated with the County's Engineering staff upon completion of a Geotechnical report which will be required prior to final plat / site plan approval.

Per Sect. 4.1.7 of SWM Code, the applicant will control the 2 & 10 yr storm events in the proposed SWM Facilities. In addition, the Applicant has agreed to provide overland relief for the 100 year storm event.

8. No stormwater runoff generated from new development shall be discharged into jurisdictional wetland without adequate treatment.

This is understood and accepted by the Applicant. Please reference the CDP, a note has been added to reflect this comment.

9. An overlot grading plan is to be provided as part of the Final Construction Plans. It is to show downspout discharges and sump pump discharges.

The Applicant will provide an overall lot grading plan as part of the Final Construction Plans. However, the locations of downspouts and sump pump discharges will not be shown on the overall lot plan due to the optional architecture that will be available for each lot.

| | Individual Lot grading plans will be provided with the building permit applications that will |
|--|---|
| | show downspout & sump pump locations |
| | along with detailed lot grading that can be |
| · | reviewed for drainage purposes. |
| 10. A second access point should be provided | See Proffer 11.9, which addresses this |
| prior to the 100 th lot being recorded. | comment. |
| 11. Proof of provisions for adequate fire flow | A Water Study will be prepared and submitted |
| as outlined by the Office of Emergency | with the Final Construction Plans. See |
| Services will be required with the first | response above with regards to the Natural |
| submission of the Final Construction Plans. | Drainage/Channel locations onsite and the |
| Houses are not to be located in existing swales | siting of lots. |
| or streams. These areas shall be preserved to | |
| the maximum extent practicable. | |
| 12. Houses are not to be located in existing | See response above with regards to the Natural |
| swales or streams. These areas shall be | Drainage/Channel locations onsite and the |
| preserved to the maximum extent practicable. | siting of lots. |
| | |
| 13. It appears that almost all of the area east of | See response under #6 above. |
| Bowen's Run has soils characterized as having | |
| a high water table. The area west of Bowen's | |
| Run has roughly 50% of the soils that are | , |
| characterized as having a high water table. | |
| 14. Site distance is to be provided for | This is understood and acknowledged by the |
| alley/street connections. Site distance will also | Applicant. Please reference the CDP, a note |
| be necessary when entering alley from the | has been added to reflect this comment. |
| garages. Garages should be set back away | |
| from the alley so a driver can see when | |
| backing out of a garage before entering alley. | · |
| 15. If the alley does not have an outlet, some | Please reference page 27 of the "Freedom |
| type of turn around is to be provided. | Place: Planning and Design Guidelines and |
| | PRD Modifications." A modification is |
| | requested to permit dead end alleys in certain |
| , | places, especially along Church Street, in order |
| | to limit excessive curb cuts. A maximum of |
| | three residential units access each of the dead |
| | ends. This coupled with restrictions in the |
| | HOA documents prohibiting conversion of |
| | garage spaces for uses other than parking, will |
| | provide sufficient space for turn arounds. |
| 16. Infiltration trenches are not allowed for | This is understood and acknowledged by the |

REZN05-LE-001, SPEX05-LE-008, Freedom Place Engineering/VDOT Response Letter March 10, 2006 Page 6 of 10

| SWM/BMP facilities in residential | Applicant. No Infiltration facilities are |
|---|---|
| subdivisions. | proposed with the plan. |
| 17. WSA's permission will be required to | This is understood and acknowledged by the |
| relocate their access roads. | applicant. |
| 18. Each phase of the subdivision must meet | An overall SWM/BMP plan has been |
| the minimum requirements of the SWM | developed for the Rezoning. The individual |
| Ordinance as well as the overall project | sections of the subdivision will be designed in |
| | substantial conformance with the CDP and |
| | calculations will be provided with the final |
| | construction plans to show that the |
| | requirements of the SWM ordinance have been |
| | met for the overall project. The Applicant will |
| | not proceed with a phase of the subdivision |
| | without either providing SWM in that section |
| | or having provided it in a prior phase of the |
| | subdivision process. |
| | |
| | I I DOME |
| 19. The termination point of existing Bower's | VDOT has requested a hammerhead terminus |
| Run Road should have a cul-de-sac. | at this location. |
| 20. Credit for vegetative filter strips (buffers) | |
| are to meet the design guide lines in the | This is understood and acknowledged by the |
| Virginia Stormwater Management Handbook | Applicant. The calculations have been revised |
| Minimum Standard 3.14. The phosphorus | accordingly. |
| removal credit is 10%. | |

The following responses are based on VDOT comments dated January 18th, 2006 on the Traffic Impact Study for Freedom Place (dated December 19th, 2005):

| Comment | Response |
|--|--|
| 1. After further review of the internal | As stated in the Land Development Manual Chapter |
| capture rates used in the Traffic Impact | 6-5 Policy Section Number 4, "In case the proposed |
| Analysis and the Land Development | multi-use development has residential and non- |
| Manual, VDOT policy indicates on | residential components, a 15% reduction in the trip |
| Chapter 6-4 that shopping centers, and | generation will be allowed." The Traffic Group, Inc. |
| general office building with support | used an ITE approved updated methodology to |
| services already have allowed for | determine internal capture and used 14%. Therefore, |
| internal capture in their traffic | we under estimated the internal capture by 1%. |
| distributions and should no include any | |

REZN05-LE-001, SPEX05-LE-008, Freedom Place Engineering/VDOT Response Letter March 10, 2006 Page 7 of 10

| | | additional internal capture. Therefore, |
|-----|---|--|
| | | the use of ITE codes 710 and 820 as |
| | | used in this Traffic Impact Analysis |
| | | should not allow for any additional |
| | | capture, and those trips should be added |
| | | to the total trips on Exhibit 8B on page |
| | | 23. The comment response indicates |
| | | that the Land Development Manual |
| | | recommends using the most up-to-date |
| | | and reliable information, but this is |
| | | only for trip generation not internal |
| | | capture. Internal capture was also |
| | | _ - |
| | | |
| | | |
| | | |
| | | |
| | ι | · |
| | | <u> </u> |
| | This was discussed in our meeting on February 22, | 2. We have also looked at whether |
| | 2006 and it was our understanding from the meeting | taking pass-by trips is appropriate |
| | that after explaining pass-by trips, our method was | |
| | appropriate. | site within the development and the |
| | | method of access. |
| 0 | The Synchro/SimTraffic Analysis will be provided to | 3. On page 84 of the Traffic Impact |
| | VDOT along with this comment/response letter. | Analysis the queue lengths for the |
| | | intersection of Route 17 and 28 are |
| | | indicating that the 95 th percentile |
| | | volume exceeds capacity and the |
| | · | queues may be longer. The queue |
| | | indicated is 1101', but it appears it may |
| | | be longer. Animation of the |
| | | intersection through Synchro may be |
| | | helpful in demonstrating the impact on |
| | | this intersection. |
| s | The Developer will review the available ROW at this | 4. The revised Traffic Impact Analysis |
| | intersection and will provide a separate right turn, if | and concept development plan are |
| | possible within the existing righ-of-way. | indicating a combined thru and right- |
| | | turn lane on Route 28, but the |
| | | Department would not support the |
| | | elimination of the existing right-turn |
| t i | This was discussed in our meeting on February 22, 2006 and it was our understanding from the meeting that after explaining pass-by trips, our method was appropriate. The Synchro/SimTraffic Analysis will be provided VDOT along with this comment/response letter. The Developer will review the available ROW at the intersection and will provide a separate right turn, it | based on the location of the commercial site within the development and the method of access. 3. On page 84 of the Traffic Impact Analysis the queue lengths for the intersection of Route 17 and 28 are indicating that the 95 th percentile volume exceeds capacity and the queues may be longer. The queue indicated is 1101', but it appears it may be longer. Animation of the intersection through Synchro may be helpful in demonstrating the impact on this intersection. 4. The revised Traffic Impact Analysis and concept development plan are |

REZN05-LE-001, SPEX05-LE-008, Freedom Place Engineering/VDOT Response Letter March 10, 2006 Page 8 of 10

| 1 D4- 20 - 1 1 1 1 1 | |
|---|---|
| lanes on Route 28 and combining them | |
| with the thru movement. | 11 1700 |
| 5. Page 30 of the Traffic Impact | As requested by VDOT, separate right turn lanes will |
| Analysis demonstrates that the | be provided on VA 28 @ US 17 and the intersection |
| following: | and each approach LOS has been mitigated to meet |
| a) Route 17 and 28 westbound | background traffic conditions. See Proffer 11.1.3. |
| approach is deteriorating from an LOS | |
| of "E" to LOS "F", but even with the | |
| mitigation measures has not been | |
| mitigated to meet background traffic | |
| conditions. | · |
| 5b) Route 28 and southwest access are | This was discussed in our meeting on February 22, |
| deteriorating from an LOS "C" to LOS | 2006 and the Developer has agreed to provide two |
| "F" with the development, but no | outbound lanes as mitigation. |
| mitigation measures have been | |
| provided. An asterisk is shown for the | |
| delay on the northbound approach. | |
| This is a new intersection being created | |
| by the subdivision, and needs to meet a | |
| minimum level of service of "C". | |
| 5c) Route 28 and Oak Shade Road | This was discussed in our meeting on February 22, |
| (Route 661) is shown with a level of | 2006 and it was our understanding that VDOT has an |
| service "F" at background and for total | ongoing project at this location and VDOT would |
| with the development, but the delay | make any necessary improvements. |
| increase from 176.9 to 249.6 and no | make any necessary improvements. |
| mitigation measures have been | |
| indicated. The improved results are | |
| incorrectly indicating a LOS of "E". | · |
| rather than "F". VDOT is evaluating a | |
| project at this intersection to construct a | |
| left-turn lane, and the intersection could | |
| be evaluated with and without the turn | · |
| lane. | |
| 6. No resolution has been reached as to | Since Church Street is designed as nor the |
| the proposed location of the Church | Since Church Street is designed as per the Comprehensive Plan, the proximity to US 17 along |
| Street and Route 28 intersection and its | , <u> </u> |
| | VA 28 has been accepted. |
| proximity to the intersection of Route | |
| 17. | Command 14 man address of the MTC (Pall 1) 14 4 |
| 7. Comments 14 and 15 from our | Comment 14 was addressed in the TIS (Exhibits 11A |
| November 16, 2005 letter only are | and 11B have several intersections that the delay has |
| indicated as being acknowledged, but | not been provided in order to evaluate the increase in |

REZN05-LE-001, SPEX05-LE-008, Freedom Place Engineering/VDOT Response Letter March 10, 2006 Page 9 of 10

| do not appear to have been revised on the Traffic Impact Analysis. | delay between background and total traffic). Comment 15 will be addressed at Site Plan since the improvement and access plans will be prepared at that. |
|---|---|
| 8. Sheet 7 of the Concept Development Plan does not indicate which of the streets will be constructed with each of the typical sections. Street widths will need to be determined based on anticipated traffic counts, and will not necessarily be the same width for all state maintained roads. Streets that are intended to be state maintained will need to be in conformance with the 2005 Subdivision Street Requirement Manual and Road Design Manual. Right-of-way widths should be even. | Please reference Sheet 9 of the GDP Talk to Bowman |
| 9. We recommend a four lane divided road section for Church Street rather than a 4 lane undivided road. | A concept plan for Church Street has been prepared and submitted to Fauquier County. This concept will be discussed between Fauquier County and VDOT. |

Sincerely,

WALSH, COLUCCI, LUBELEY, EMRICH & TERPAK, P.C.

Wanda S. Suder, AICP Planner

WSS/wss

cc: Andrew Vinisky, Project Manager, Centex Homes
Heather Himes, Centex Homes
Donald H. Hughes, Engineering Manager, Centex Homes - DC Metro
Mark Tauscher, Bowman Consulting Group
Jonathan Bondi, Bowman Consulting

REZN05-LE-001, SPEX05-LE-008, Freedom Place Engineering/VDOT Response Letter March 10, 2006 Page 10 of 10

> Joe Calogerro, The Traffic Group John Foote, WCLET