HIGH SCHOOL #3 PROJECT COSTS

Based on Howard Shockey & Sons, Inc. Low Bid

PROJECT COSTS

Construction Costs

TOTAL PROJECT FUNDING

Base Bid (Shoo Site Costs Subtotal Base	41,056,000 10,254,000	51,310,000				
Bid Alt #2: Bid Alt #3: Bid Alt #4:		700,000 616,300 32,700 370,500 421,000	2,140,500 53,450,500			
Additional WSA Project Manage Wetland Mitigat FF&E (8% build	4.0% tions, and other Professional Fees Connection Fee ement (@70,000 X 2 years) ion Credits lling related costs)	2,138,020 1,579,492 3,800,000 1,069,010 270,523 140,000 154,625 3,350,000				
Fueling Facility Easements and Roadway Impro Subtotal Other	vements	1,500,000 TBD TBD	14,001,670 67,452,170			
PROJECT FUNDING						
FY 2006 CIP For FY 2007 CIP For Cash	-	19,806,000 36,694,000 11,000,000				

67,500,000

FAUQUIER COUNTY HIGH SCHOOL #3 Cost Estimate Comparisons

		SD Estimate * 11/8/2004	Final Estimate 7/29/2005	% Change
Building and Alternates		32,784,955	34,602,418	5.54%
On-Site Costs		5,126,437	7,333,038	43.04%
Off-Site Costs		1,281,547	1,323,827	3.30%
Contingency		2,990,518		
	Subtotal	42,183,457	43,259,283	2.55%
Other Costs	_	10,497,447	10,761,025	2.51%
	_	52,680,904	54,020,308	2.54%

^{* 2} months of escalation added for Bid Date of August instead of June

	Moseley Estimate	Revised Estimate		
	as of Nov-04	Aug-05	% Change	31,053,226 Building Cost 1,325,000 Alternatives
Building	31,053,226	33,168,601	6.81%	32,378,226 Subtotal Bldg. Costs 2,484,258 8% contingency on Bldg. Cost only
Plus: Alternates Included in CIP Submission				34,862,484 Bldg Costs + 8% cont. on Bldg. Cost only
Grandstands @ Competition Fields	550,000			406,729 2 months escalation on Bldg Cost & 8% cont. on Bldg Cost
Concession/Toilets/Storage Press Boxes (3)	550,000 75,000			35,269,213
Plus: Alternates Not Included in CIP Submission	75,000			
Greenhouse	120,000			
Maintenance Shed	30,000			
Total Add Alternates	1,325,000			
2 Months Escalation for Change in Bid Date	406,729			
Adjusted Building & Alternates Costs	32,784,955	33,168,601	1.17%	4,689,048 On-Site site work 373,600 Wetland mitigation
Site Costs				5,062,648 Subtotal
On site	4,689,048	7,029,179		405,012 8% contingency
Wetlands Mitigation	373,600			
2 Months Escalation for Change in Bid Date	63,789			
Subtotal On Site Costs	5,126,437			
Off site	1,265,600	1,268,972		5,467,660
2 Months Escalation for Change in Bid Date	15,947			
Subtotal Off Site Costs	1,281,547	0.000.454	00.500/	00.700 0 4 4 4
Total Site Costs	6,407,984	8,298,151	29.50%	63,789 2 months escalation
Building, Alternates & Site Subtotal	39,192,939	41,466,752	5.80%	5,531,449 Total on-site work
Area Cost Factor at .90		37,320,076		
Design & Construction Contingency	2,990,518	1,492,803		1,265,600 off site improvements 1492803
Overhead & Profit @8%		3,105,030		
Escalation at 3.5% to Mid-Point		1,341,373		1,366,848 Subtotal 2834176
				15,947 2 months escalation
Subtotal Construction/Contingency/Site Costs	42,183,457	43,259,282	2.55%	1,382,795
Other costs				
A&E Fees (7.5%)	3,163,759	3,244,446		
FF&E (15%)	6,327,518.54	6,488,892.30		42,183,457
Testing and special inspections (2%)	843,669	865,186		
Project management (@\$65,000 * 2.5 yrs.)	162,500	162,500		
Subtotal other costs	10,497,447	10,761,024		
TOTAL PROJECT COST	52,680,904	54,020,306	2.54%	

Opinion of Probable Cost

Opinion of Probable Cost	Conceptual Phase 11/10/05	Conceptual Phase 09/14/04
On-site Improvements		_
Erosion Control	175,000	87,000
Clearing		
Clearing	420,000	232,000
Stripping	210,000	139,200
Topsoil disposal	-	
Total clearing	630,000	371,200
Demotion	-	-
Earthwork		
Excavation	1,006,200	210,000
Fine grading	168,000	140,000
Total earthwork	1,174,200	350,000
Allowances		
Additional excavation	-	120,000
Rock excavation (assumes 20%)	3,120,000	120,000
Total allowances	3,120,000	240,000
Utilities		
Sanitary sewer (gravity)	102,000	144,000
Waterline	357,000	145,600
Total utilities	459,000	289,600
Drainage		
Drainage structures	350,000	108,000
Storm sewer	612,000	245,000
Roof drains	54,000	54,000
Stormwater management	80,000	45,000
Underdrains	28,500	12,000
Total drainage	1,124,500	464,000
Paving		
Pavement - heavy duty	935,000	194,000
Pavement - light duty	380,000	512,000
Pavement - recreational	-	195,600
Concrete pavement	60,000	100,800
Total paving	1,375,000	1,002,400
Site Concrete		
Curb & gutter	273,000	189,600
Walks	179,200	700,000
Total concrete	452,200	889,600
Miscellaneous		
Pavement markings	18,275	4,000
Signage	6,000	8,000
Athletic surfacing	600,000	100,000
Total miscellaneous	624,275	112,000

Fencing

Perimeter fencing	48,000	50,400
Athletic field fencing	63,000	43,400
Total fencing	111,000	93,800
Landscaping		
Topsoil & seed	147,000	100,000
Landscaping allowance	100,000	100,000
Irrigation	50,000	50,000
Total Landscaping	297,000	250,000
Subtotal sitework	9,542,175	4,149,600
8% Contractors OH&P	763,374	331,968
5% Design contingency	700,074	207,480
Total On alta lunnanumanta	40 005 540	4 000 040
Total On-site Improvements	10,305,549	4,689,048
Off-site Improvements		
Road improvements		
Turn lanes road widening	500,000	500,000
Signalized intx for school entrance	150,000	150,000
Total road improvements	650,000	650,000
Utility improvements		
Waterline (12")		150,000
Sewer (4" force main)	162,000	120,000
Sanitary sewer (pump station)	200,000	200,000
Total utility improvements	362,000	470,000
Subtotal off-site improvements	1,012,000	1,120,000
8% Contractors OH&P	80,960	89,600
5% Design contingency	00,000	56,000
Total off-site improvements	1,092,960	1,265,600
Total on-site improvements	1,092,900	1,265,600
Additional Development Costs		
Wetlands mitigation		20,000
Relocation of existing utilities	40= 000	200,000
Water connection fees (2" meters assumed)	105,600	105,600
Sewer connection fee (based on 2" water me R/W or easement acquisition costs	48,000	48,000
Subtotal additional development costs	153,600	373,600
8% Contractors OH&P	12,288	373,000
0/0 CONTRACTORS OF ICE	12,200	
Total additional development costs	165,888	373,600
_		
Project Total	11,564,397	6,328,248

Alternate

Bus Storage		
Erosion control	20,000	
Clearing	48,000	
Stripping	24,000	
Excavation	85,800	
Fine grading	32,000	
Rock excavation	264,000	
Pavement - heavy duty	390,000	
Pavement markings	2,380	
Perimeter fencing	14,400	
Subtotal bus storage/fueling	880,580	
8% Contractors OH&P	70,446	
Total Alternate	951,026	-

Omissions

Bleachers Grandstands Site lighting